

Volume Report
Subgrade vs. Stripped

	Total	Cut	Area	Fill	OnGrade	Volume	Fill	Comp/Ratio	Comp	Export	Change
						Cut		Cut	Fill	Per	1 Ft
Asphalt.1 Pave HD	87,966	75,145	9,864	2,957	8,660	279	1.00	8,660	279	8,381	326
Asphalt.1 Pave HD	8,927	8,905	10	12	1,061	0	1.00	1,061	0	1,061	33
Asphalt.1 Sub:	96,893	84,050	9,874	2,969	9,721	279		9,721	279	9,442	359
Asphalt.2 Pave LD	48,848	39,221	8,091	1,536	2,040	505	1.00	2,040	505	1,535	181
Asphalt.2 Pave LD	4,035	0	4,035	0	0	261	1.00	0	261	-261	15
Asphalt.2 Sub:	52,883	39,221	12,126	1,536	2,040	766		2,040	766	1,274	196
Building	131,759	6,326	119,452	5,981	55	7,532	1.00	55	7,532	-7,477	488
Concrete Pave (Dolly Rest)	2,654	2,654	0	0	381	0	1.00	381	0	381	10
Concrete Pave (Loading Doc Area)	36,987	28,564	6,479	1,944	3,795	233	1.00	3,795	233	3,562	137
Concrete Sub:	39,641	31,218	6,479	1,944	4,176	233		4,176	233	3,943	147
Concrete Sidewalk	4,231	2,300	1,743	188	45	87	1.00	45	87	-42	16
Topsoil.2 Tight	9,017	0	9,017	0	0	1,213	1.00	0	1,213	-1,213	33
Topsoil.2 Tight	31,214	2,467	26,216	2,531	31	1,387	1.00	31	1,387	-1,356	116
Topsoil.2 Tight	24,352	4,143	19,398	811	153	872	1.00	153	872	-719	90
Topsoil.2 Tight	3,245	1,541	1,263	441	41	22	1.00	41	22	-19	12
Topsoil.2 Tight	18,917	10,900	6,531	1,486	713	210	1.00	713	210	503	70
Topsoil.2 Tight	9,432	9,432	0	0	1,291	0	1.00	1,291	0	1,291	35
Topsoil.2 Sub:	96,177	28,483	62,425	5,269	2,229	3,704		2,229	3,704	-1,475	356
Topsoil.3 Islands	7,934	5,340	1,079	1,515	87	11	1.00	87	11	76	29
Topsoil.3 Islands	2,606	386	2,038	182	4	195	1.00	4	195	-191	10
Topsoil.3 Islands	929	929	0	0	127	0	1.00	127	0	127	3
Topsoil.3 Islands	652	438	87	127	5	1	1.00	5	1	4	2
Topsoil.3 Islands	301	0	301	0	0	10	1.00	0	10	-10	1
Topsoil.3 Islands	289	0	289	0	0	29	1.00	0	29	-29	1
Topsoil.3 Islands	288	0	286	2	0	25	1.00	0	25	-25	1
Topsoil.3 Islands	237	174	29	34	4	0	1.00	4	0	4	1
Topsoil.3 Islands	5,283	1,771	3,441	71	43	181	1.00	43	181	-138	20
Topsoil.3 Islands	398	0	398	0	0	14	1.00	0	14	-14	1
Topsoil.3 Sub:	18,917	9,038	7,948	1,931	270	466		270	466	-196	69
Regions Total	440,501	200,636	220,047	19,818	18,536	13,067		18,536	13,067	5,469	1,631

Stripping Qty's	Plane Area	Slope Area	Depth	Volume
Strip Topsoil	440,510	441,005	0.750	12,250

Sectional Qty's	Plane Area	Slope Area	Depth	Volume
Asphalt.1 Pave HD	8,927	8,982	0.583	194
Asphalt.1 Pave HD	87,966	88,243	0.583	1,905

Asphalt.1 Sub:	96,893	97,225	2,099
----------------	--------	--------	-------

Asphalt.2 Pave LD	48,848	49,152	759
Asphalt.2 Pave LD	4,035	4,086	63

Asphalt.2 Sub:	52,883	53,238	822
----------------	--------	--------	-----

Building	131,759	131,759	2,845
----------	---------	---------	-------

Concrete Pave (Dolly Rest)	2,654	2,659	49
Concrete Pave (Loading Doc Area)	36,986	37,030	686

Concrete Sub:	39,640	39,689	735
---------------	--------	--------	-----

Concrete Sidewalk	4,231	4,238	52
-------------------	-------	-------	----

Topsoil.2 Tight	9,432	9,434	175
-----------------	-------	-------	-----

Sectional Qty's	Plane Area	Slope Area	Depth	Volume
Topsoil.2 Tight	9,017	9,072	0.500	168
Topsoil.2 Tight	18,917	19,162	0.500	355
Topsoil.2 Tight	31,214	31,421	0.500	582
Topsoil.2 Tight	24,352	24,704	0.500	457
Topsoil.2 Tight	3,245	3,263	0.500	60

Topsoil.2 Sub:	96,177	97,056	1,797
----------------	--------	--------	-------

Topsoil.3 Islands	7,934	7,961	0.500	147
Topsoil.3 Islands	2,606	2,615	0.500	48
Topsoil.3 Islands	289	289	0.500	5
Topsoil.3 Islands	288	289	0.500	5
Topsoil.3 Islands	929	929	0.500	17
Topsoil.3 Islands	237	238	0.500	4
Topsoil.3 Islands	652	654	0.500	12
Topsoil.3 Islands	301	301	0.500	6
Topsoil.3 Islands	398	398	0.500	7
Topsoil.3 Islands	5,283	5,301	0.500	98

Topsoil.3 Sub:	18,917	18,975	349
----------------	--------	--------	-----

Sectional Total	440,500	442,180	8,699
-----------------	---------	---------	-------

